

abn: 56 291 496 553

3/69 Centennial Circuit, Byron Bay, NSW, 2481

PO Box 538, Lennox Head, NSW, 2478

Telephone: 1300 66 00 87

26 July 2017

Our reference: 1540.1949

NSW Coastal Panel

Attention: Mr Marc Daley

Email: coastal.panel@environment.nsw.gov.au cc. marc.daley@environment.nsw.gov.au

Dear Mr Daley

RE: Development Application (DA) CP17-004, Lots 32-36 Section 2 DP 1623, Nos. 28 & 28A Childe Street, Byron Bay

We refer to previous correspondence in relation to the above development application including our most recent letter dated 10 July 2017.

Please find attached a copy of revised plans for the Belongil Seawall repairs prepared by International Coastal Management, dated 24 July 2017. As is evident from the revised plans, the repairs have been amended to provide a 0.5m setback from Crown Land to assist in ensuring that works do not encroach onto the Crown Land. The revised plans also depict the proposed erection of a safety fence and signage and the proposed temporary construction access along Council Land to enable the repairs. As also detailed in the Repair Construction Method Statement, test excavations along the wall on Council Land during the construction phase will be undertaken to assess the condition of the secondary armour and filter layers of the wall and the extent of the repair works required to those layers.

In relation to the potential environmental impacts of the development as revised, as detailed in the Statement of Environmental Effects submitted with the initial Development Application, the further information provided by International Coastal Management to the Coastal Panel and the Construction Notes on plan 010, Rev D (enclosed) prepared by International Coastal Management, the proposed works seek to make safe the existing wall on Council Land by removing any loose rocks and damaged sections of the wall and restacking the loose rocks to form a stable slope. The filter layer and secondary armour layer of the wall will also be repaired, as required following the test excavations, to ensure a stable slope is restored. The repair works will also improve the security of the public walkway above the beach. It is submitted that the proposed repair works will improve public safety and will not pose a threat to public safety. As concluded in the material prepared by International Coastal Management, any impacts on the beach and adjacent land will be the same, or less than at present. That is, the repairs will not cause any increased erosion of the beach or adjacent land.

We submit that the proposed works are consistent with relevant statutory and policy provisions as detailed in the Statement of Environmental Effects submitted with the Development Application. In the event that the Crown requests, the proponent is also agreeable to removing strewn rock from the beach.



We trust that the revised plans submitted satisfactorily address your concerns and clarify the extent of the proposed works, confirming that no works are proposed on Crown Land. Please do not hesitate to contact us should you wish to clarify any matter raised by this advice.

Yours faithfully,

PLANNERS NORTH



Kate Singleton MPIA CPP

PARTNERSHIP PRINCIPAL

(m) 0438 803 021

(e) kate@plannersnorth.com.au

Encl. Revised plans





OFFICE 50G 1 MacArthur Parade, Main Beach, 4217, QLD, Australia POST PO Box 306, Main Beach LPO, Main Beach QLD, 4217, Australia TELEPHONE +61 7 55640564 FAX +61 7 55329147 WEBSITE www.coastalmanagement.com.au

Belongil Seawall Repairs

28, 28A CHILDE STREET AND 8 THE ESPLANADE (Lots 32, 33, 34, 35 and 36 in Section 2 of DP1623) DRAWINGS FOR INITIAL REPAIRS (NO WORKS ON CROWN LAND)

DRAWING REGISTER

24.07.2017

BSR - CS3 - 001 D COVER PAGE

BSR - CS3 - 002 C PLAN VIEW (PRESENT)

BSR - CS3 - 003 D X-SECTION A (PRESENT)

BSR - CS3 - 004 D REPAIR WORKS A

BSR - CS3 - 005 D X-SECTION B(PRESENT)

BSR - CS3 - 006 D REPAIR WORKS B

BSR - CS3 - 007 X-SECTION C (PRESENT)

BSR - CS3 - 008 REPAIR WORKS C

BSR - CS3 - 009 D CONSTRUCTION PLAN


BSR - CS3 - 010 D CONSTRUCTION NOTES


BSR - CS3 - 011 CANTY SURVEY 2016


BSR - CS3 - 012 A TRAFFIC CONTROL PLAN






















REPAIR DESIGN

To determine the extent of repair works:

- An inspection of the walls covered under the consent orders was carried out by ICM engineers on 13/10/16 to ascertain the present condition.
- Historical photos and surveys held by ICM were reviewed to ascertain the previous condition.

REPAIR CONSTRUCTION METHOD STATEMENT

Works to repair the seawall structures are to be carried out as anticipated by the recent Supreme Court of NSW consent orders made 12/8/16. The proposed method of carrying out the works is as follows:

- Pre-Construction
- All approvals and notifications to be in place.
- Safety fencing and signage is to erected as per drawing 007 to restrict public access to the work and access areas.
- Temporary construction access from either the sealed section of Manfred Street over the existing rock wall or, alternatively, the sealed section of Don Street along the southern boundary of 1 Don Street over the existing SFGC wall (covered with 1200gsm non-woven geotextile) onto the beach.
- Construction (5 days per week, 7am to 6pm. Estimated repair time 2 week)
- O Access onto the fenced works area for equipment and materials will be by temporary construction track.
- o For every 20m length of wall on the Council Land, a 5m wide test section of wall will be excavated back to assess the condition of the secondary armour, filter layer and the extent of the required repair works.
- O The works shall be carried out in 10 -15m sections starting from the NW end.
- O The crest and toe of the works on the Council Land shall be tapered smoothly into the adjacent crest and toe without interference with the existing structures.
- O The existing access to the beach shall be repaired and safe access provided at each end of the works to provide public access along the top of the wall.
- The wall is to be progressively surveyed and final "as constructed" drawings prepared.
- Post-Construction
- If requested by Crown Lands, strewn rock from that part of the beach owned by Crown Lands to be removed.
- O The access track is to be restored to the original condition.
- The safety fencing is to be removed.
- Repair Costs
- O Preliminary Estimate = \$165,000

MITIGATION OF IMPACTS

The works have been designed to avoid adverse impacts. Section 55M of the Coastal Protection Act requires that: (a) the works will not over the life of the works:

- (i) unreasonably limit or be likely to unreasonably limit public access to or the use of a beach or headland, or (ii) pose or be likely to pose a threat to public safety, and
- (b) satisfactory arrangements have been made (by conditions imposed on the consent) for the following for the life of the works:
 - (i) the restoration of a beach, or land adjacent to the beach, if any increased erosion of the beach or adjacent land is caused by the presence of the works,
 - (ii) the maintenance of the works.

With reference to the above conditions

Re (a) (i):

- The proposed works on the Council Land are to make safe existing works by removing loose and damaged sections of wall as per the initial test excavations and assessing the condition of the secondary armour and filter layer. The filter layer and wall armour is to then be repaired by restacking those sections of wall that were removed back onto the wall to restore a stable slope without loose rocks that could be easily dislodged during erosion events.
- The completed repair works will improve the security of the public walkway above the beach.

Re(a) (ii);

• The proposed repair works will improve public safety by restacking loose rock. Thus, the repair works will not "pose a threat to public safety".

Re (b) (i);

• The proposed repair works will restore a stable slope. Loose rocks from that part of the Council Land will be moved landward onto the steeper slope of the wall. The repaired wall face will also be less reflective during erosion events. As a result, any impacts on the beach and adjacent land will be the same, or less, than at present. Thus, the repairs will not cause "any increased erosion of the beach or adjacent land".

Re (b) (ii);

The proposed repair works can and should be maintained by the landowners after each erosion event that impacts the wall.

NOTES

LOCALITY PLAN

LEGEND

Ľ	VERTIC	AL DATU	M: AHD HORIZONTAL D	ATUM:	-	
Γ	REV	ISION	REGISTER			
ſ	-	-				
I	-	-	·	-		-
	D	D 10/7/17 Removed work on Crown Land		SK	AJ	AJ
	С	14/06/17	Amended Construction Notes	SK	AJ	AJ
	В	21/04/17	Amended Construction Notes	SK	AJ	AJ
	Α	15/03/17	Ameneded Construction Notes	SK	AJ	AJ
F	REV.NO.	DATE	DESCRIPTION	BY	ENG.	APP.



OJECT NAME

BELONGIL SEAWALL REPAIRS


CONSTRUCTION NOTES


DRAWING No.

BSR - CS3 - 010

RPEQ 2876
SCALE : A3 DATE : 24 Jul, 2017

D





TRAFFIC CONTROL PLAN

NOTES

- 1. Work hours; 7am 6pm Monday to Friday excepting public holidays
- 2. Construction Time; Approx 10 working days.
- 3. Truck volumes; It is estimated that 60 trucks @ 12t/truck over the 10 days will be required.
- Traffic Control and Signage; All traffic control and signage is to comply with Roads & Maritime Services Guide to Traffic Control at Worksites Manual. All signage is to be removed when works are not in progress and are to be removed immediately following the completion of works.
- Sign distances may be shortened to 25m so not to be obscured by vegetation if necessary.
- Traffic controller to hold North bound traffic for truck to reverse into sight
- Contractor to provide a spotter for vehicles and pedestrians in Manfred St.
- 5. Road Hazards; Trucking operations to be implemented in a safe manner so as to not cause a hazard for motorists or pedestrians.
- Covering of Loads; All loads are to be covered with taut heavy duty purpose fitted tarpaulins to ensure no loss of load or dust.
- 7. Mud; Contractor to ensure that the wheels, tracks and body surfaces of all vehicles and plant leaving the site are free of mud and that mud is not carried on to adjaced paved streets or other areas.

VERTIC	AL DATU	M: -		HORIZONTA	L DATUM:	-	
REV	ISION	REGIS	STER				
	-			-	-		
-	-				-	-	
-	-			-	-		-
-	-			-		Г	
-	-			-			
Α	10/7/17		Added Ro	SK	AJ	Α.	
REV.NO.	DATE		DESCR	IPTION	BY	ENG.	AF
	28A CH		STREET	AND 8 T	HE ESF	PLAN	ΑD
DRAW	TRA	-	CON	TROL	PLAN		
DRAWI	NG No.					REVI	NOIS
	E	BSR -	CS3	- 012		Α	
DRAWN	I: SK		CHECKED :	AJ	APPROVE	D : AJ	
						RPE	Q 2